

STATE	FOREST	PROJECT NAME	SHEET	SHEETS
IDAHO	CLW	WHITE-WHITE ROAD DECOMMISSIONING	2	29

SUMMARY OF ESTIMATED QUANTITIES

FOR INFORMATIONAL PURPOSES ONLY

ROAD DECOMMISSIONING - PRIORITY

NO. ITEM	ITEM DESCRIPTION	UNIT	5026-A	5027	5027-B	5133	5135-A	73024	73025	73038	850112	850142	850145	TOTAL
			0-0.26	.8-1.06	0-0.34	.22-1.19	0-0.84	0-1.19	0-0.47	0-1.32	0-0.02	0-0.26	0-0.45	
15101	MOBILIZATION	LS	ALL REQUIRED											1
15707	BALES, STRAW	EACH	0	12	0	4	16	4	4	4	8	4	0	56
20301	REMOVAL OF METAL CULVERTS	EACH	1	6	5	3	0	0	0	1	0	0	0	16
21103A	ROADWAY OBLITERATION, METHOD I	MI	0.26	0.98	0.34	0.97	0	0.61	0.47	0.71	0.02	0.26	0.45	5.07
21103B	ROADWAY OBLITERATION, METHOD II	MI	0	0	0	0	0.84	0.58	0	0.61	0	0	0	2.03
62201	HYDRAULIC EXCAVATOR WITH THUMB	HOUR	0	6	0	2	8	2	2	2	8	2	0	32
62501	SEEDING, DRY METHOD	ACRE	1.10	3.90	1.40	3.90	3.40	4.80	1.90	5.30	0.10	1.00	1.80	28.60

ROAD DECOMMISSIONING - OPTIONAL

NO. ITEM	ITEM DESCRIPTION	UNIT	521-D	523-B	523-E	575	5179	73041	850146	850147	TOTAL
			0-1.06	0-0.92	0-0.30	0-0.16	0.4-1.15	0-0.59	0-0.53	0-0.54	
15707	BALES, STRAW	EACH	12	8	0	4	8	4	0	0	36
20301	REMOVAL OF METAL CULVERTS	EACH	8	5	3	1	6	1	0	0	24
21103A	ROADWAY OBLITERATION, METHOD I	MI	0	0.92	0.30	0.16	0.75	0.59	0.53	0.54	3.79
21103B	ROADWAY OBLITERATION, METHOD II	MI	1.19	0	0	0	0	0	0	0	1.19
62201	HYDRAULIC EXCAVATOR WITH THUMB	HOUR	6	4	0	2	4	2	0	0	18
62501	SEEDING, DRY METHOD	ACRE	4.80	3.70	1.20	0.70	3.00	2.40	2.10	2.20	20.10

OPTIONAL ROAD DECOMMISSIONING WILL BE CHOSEN BY THE INDIVIDUAL ROAD AND BE BASED ON AVAILABLE FUNDING.

NOTES

- ITEM 15707 STRAW BALES ARE TO BE USED FOR EROSION CONTROL FOR SUCH THINGS AS CHECK DAMS AND MULCH AS DIRECTED BY THE C.O.
- ITEM 20301 ALL METAL CULVERT DESIGNATED FOR REMOVAL SHALL BECOME THE PROPERTY OF THE CONTRACTOR AND BE REMOVED FROM FOREST LAND AND DISPOSED OF IN A LEGAL MANNER.
- ITEM 21103 ALL LIVE STREAMS WILL REQUIRE EITHER THE EXISTING CULVERT OR A TEMPORARY CULVERT WHEN CROSSING FOR ACCESS
- AND WILL REQUIRE DEWATERING OR STREAM DIVERSIONS WHEN DOING CHANNEL WORK.
- ITEM 21103 ROAD OBLITERATION METHODS VARY BY INDIVIDUAL ROAD AND ARE SPECIFICALLY NOTED ON THE WORK LISTS.
- ITEM 21103 WORKLISTS ARE DETERMINED FROM OLD SURVEYS AND WORK LISTED IS A BEST ESTIMATE. CONDITIONS MAY HAVE CHANGED ON THE GROUND.
- ALL REQUIREMENTS OF SPECIFICATION 211 SHALL BE MET.
- ITEM 62201 EQUIPMENT RENTAL WORK IS FOR UNFORSEEN SITUATIONS. ALL WORK WILL BE APPROVED BY THE C.O. PRIOR TO EXECUTION. THIS ITEM MAY NOT BE USED IN ITS ENTIRETY.