

DESCRIPTION OF PROJECT:

Project Number: WA FS ERFO 2007(1)-20(18)

Project Name: Coal Lake Road and Mallardy Creek Bridge Emergency Repairs

0.05 **Miles**

Description & type of Work: This work consists of grading, drainage, rock embankment, aggregate base and surfacing, and paving.

LOCATION:

FOREST, PARK, BLM DIST, etc. Mt. Baker – Snoqualmie National Forest

COUNTY Snohomish **STATE** Washington

THIS PROJECT IS LOCATED APPROXIMATELY:

43 Miles East
of Everett Washington
(City) (State)

PRICE RANGE:

x Under \$500,000

CONTRACT TIME – The Government Estimate is based on:**FIXED COMPLETION****SCHEDULE**

(indicate # of schedules)

x

DATE

(required information)

September 30, 2008

One Schedule

DESCRIPTION OF WORK:

☒ **US CUSTOMARY UNITS**

DIVISION 150 – Project Requirements

152	Construction Survey & Staking	x	YES		NO
155	Schedules for Construction Contracts (<i>construction schedules</i>)	x	YES		NO
157	Soil Erosion Control Devices (<i>erosion control devices</i>)				
	Sediment Wattles			710 lnft	
	Silt Fence			152 lnft	

DIVISION 200 – Earthwork

201	Clearing & Grubbing	0.1 acre
204	Excavation & Embankment	
	Roadway excavation	53 cuyd
	Unclassified borrow	800 ton
	Select borrow	310 ton

DIVISION 250 - Slope Reinforcement and Retaining Walls

251	Riprap	131 cuyd
-----	--------	----------

DIVISION 300 – Aggregate Courses

303	Road reconditioning Aggregate surface reconditioning	267 sqyd
308	Minor Crushed Aggregate (<i>crushed aggregate</i>)	109 cuyd

DIVISION 400 – Asphalt Pavements & Surface Treatments

404	Minor Hot Asphalt Concrete (<i>asphalt concrete pavement</i>)	18.5 ton
-----	---	----------

DIVISION 600 – Incidental Construction

607	Cleaning pipe culvert	45 lnft			
622	Rental Equipment	X	YES		NO
624	Topsoil (<i>landscaping & related items</i>)	0.1 acre			
625	Turf Establishment (<i>indicate seeding or mulching separately</i>)	0.1 acre			
635	Temporary Traffic Control (<i>traffic control – flaggers & pilot cars</i>)	1 lump sum			

NOTE: QUANTITIES ARE PROVIDED FOR INFORMATION ONLY. THIS PROJECT WILL BE BID AS A LUMP SUM.