

TYPICAL DEMOLITION NOTES

- REMOVE ALL EXISTING ELECTRICAL MATERIALS AND ASSOCIATED ITEMS AS SHOWN OR NOTED ON THE DRAWINGS AND AS REQUIRED BY THE WORK.
- 2. REMOVE HEAT AND SMOKE DETECTORS AS SHOWN.
- REMOVE ALL ABANDONED WIRING, CONDUIT, FITTINGS, ETC., IN THE PROJECT AREA. CAP ALL STUBS, AND SEAL PENETRATIONS THRU WALLS AND FLOORS.
- 4. ALL CONDITIONS SHALL BE CAREFULLY FIELD DETERMINED AND VERIFIED PRIOR TO REMOVAL.
- . PROVIDE A 2 WEEK NOTICE FOR ANY POWER DISTURBANCE.

## **ELECTRICAL KEYED NOTES:**

- 1 EXISTING AUTOMATIC PROJECTOR SCREEN TO BE RELOCATED TO CENTER OF NEW ROOM
- 2 EXISTING COMPUTER CONNECTION TO PROJECTOR, TO REMAIN
- 3 EXISTING MICROPHONE OUTLET TO PROJECTOR TO REMAIN.
- PA SPEAKERS TO BE REMOVED AND RELOCATED, SEE E2.2

5	MULTIMEDIA	<b>SPEAKERS</b>	TO	BE	REMOVED	AND	RELOCATED,	SEE	E2.2

	ELECTRICAL LEGEND — DEMOLITION				
A-004	4-PORT COMMUNICATIONS OUTLET TO BE REMOVED				
<\$P>	SPEAKER TO BE REMOVED				
[F]<1 15	FIRE ALARM STROBE TO BE REMOVED				
(S)	SMOKE DETECTOR TO BE REMOVED				
(J)	JUNCTION BOX TO BE REMOVED				

PICHTHE WINE

REVISION

183rd Fighter Wing
Illinois Air National Guard



HANSON PROJECT
FILENAME E-102.DWG
SCALE 1/4" = 1'-0"
DATE 3/2/09

LAYOUT PJG 08/20/08
DRAWN PJG 01/20/09



**Hanson Professional Services Inc.** 1525 South Sixth Street **Springfield, Illinois 62703-2886**  **ELECTRICAL SPECIAL SYSTEMS-DEMOLITION** 

COMMAND POST (CP) RELOCATION 183D FIGHTER WING SPRINGFIELD, IL