

CONTROL DATA						
STATION	NORTHING	EASTING	ELEV.	DESCRIPTION		
N. END	2,646,652.19	1,660,582.43	41.39	USACE	SBC	1978 (STA 58+92.73)
S. END	2,644,298.25	1,659,725.47	40.47	USACE	SBC	1978 (STA 53+87.33)
DJ-1	2,650,309.04	1,661,821.57	181.47	—	—	—
DJ-2	2,652,477.41	1,653,265.13	46.47	—	—	—
SP-1	2,629,955.41	1,645,787.75	33.47	—	—	—
SP-1	2,632,165.12	1,650,395.14	36.47	—	—	—
SANDBAG	2,646,634.30	1,662,476.29	206.82	USC	& GS	SBC
CLIFF	2,648,978.03	1,662,106.44	250.99	—	—	—
CLIFF COR	2,642,005.53	1,660,590.81	129.99	—	—	—
ZZ-1	2,644,301.39	1,660,846.61	39.99	—	—	—

SURVEY LIMITS		
CORNER	NORTHING	EASTING
S1	2,650,729.24	1,661,635.08
S2	2,651,749.00	1,659,912.00
S3	2,641,054.00	1,656,105.00
S4	2,641,057.43	1,656,111.18
S5	2,642,400.31	1,658,601.12
S6	2,643,288.83	1,658,924.76
S7	2,643,482.52	1,659,251.58
S8	2,643,954.33	1,659,521.00
S9	2,644,084.66	1,659,718.78
S10	2,644,273.75	1,659,727.11
S11	2,644,280.74	1,659,707.85
S12	2,646,765.84	1,660,612.59
S13	2,646,800.54	1,660,524.08
S14	2,647,089.00	1,660,524.08
S15	2,647,729.40	1,660,542.33

NOTES

SURVEY LIMIT ALONG THE DOCK IS 5 FT
OFF THE FINISHED DOCK FACE.

THE SURVEY LIMIT IS THE MINIMUM
AREA OF SURVEY COVERAGE.

SURVEY LIMIT WILL CHANGE AS PORT
EXPANSION PROGRESSES FOR THE NORTH
AND SOUTH REPAIRMENT ALONG
THE NEW DOCK FACE.

DISPOSAL LIMITS		
CORNER	NORTHING	EASTING
DS1	2,642,356.04	1,653,697.24
DS2	2,650,812.98	1,656,776.26
DS3	2,650,128.76	1,658,655.55
DS4	2,641,671.82	1,655,576.56

