

**Date:** 10/04/2007 **Solicitation No.:** DTFH70-08-R-00002  
(Contracts use only)

**DESCRIPTION OF PROJECT:**

**Project Number:** MT PRA-GLAC 10(27)

**Project Name:** Rehabilitate West Entrance Station

**Project Length:** 0.320 Miles **Kilometers or Miles** (circle one)

**Description & type of Work:** This work consists of grading, base, paving, and drainage.

**LOCATION:**

**FOREST, PARK, BLM DIST, etc.** Glacier National Park

**COUNTY** Flathead **STATE** Montana

**THIS PROJECT IS LOCATED APPROXIMATELY:**

0.5 Miles North  
of West Glacier Montana  
(City) (State)

**PRICE RANGE:**

Under \$500,000

**CONTRACT TIME – The Government Estimate is based on:**

<b>SCHEDULE</b> (indicate # of schedules)	<b>FIXED COMPLETION DATE</b> (required information)
<u>One Schedule</u>	<u>5/26/2008</u>

**DESCRIPTION OF WORK (check one):**

**US CUSTOMARY UNITS**

**DIVISION 150 – Project Requirements**

152	Construction Survey & Staking	X	YES		NO
153	Contractor Quality Control and Assurance	X	YES		NO
154	Contractor Sampling & Testing	X	YES		NO
155	Schedules for Construction Contracts ( <i>construction schedules</i> )	X	YES		NO
157	Soil Erosion Control Devices ( <i>erosion control devices</i> )	Sediment Wattles – 1737 lft			

**DIVISION 200 – Earthwork**

201	Clearing & Grubbing	3911 sqyd			
202	Additional Clearing & Grubbing ( <i>clearing &amp; grubbing</i> )	Removal of individual tree – 59 each			
203	Removal of Structures & Obstructions ( <i>structures, demolition</i> )	Removal of light pole – 2 total Removal of pavement, 5-inch depth – 262 sqyd Removal of pavement, 6-inch depth – 111 sqyd			
204	Excavation & Embankment	Excavation – 938 cuyd Select borrow – 1398 cuyd			

**DIVISION 250 - Slope Reinforcement and Retaining Walls**

251	Riprap	Placed riprap, class 3- 4.5 cuyd			
-----	--------	----------------------------------	--	--	--

**DIVISION 300 – Aggregate Courses**

308	Minor Crushed Aggregate ( <i>crushed aggregate</i> )	Roadway aggregate, method 2 – 638.5 ton			
-----	--	---	--	--	--

**DIVISION 400 – Asphalt Pavements & Surface Treatments**

403	Hot Asphalt Concrete Pavement ( <i>asphalt concrete pavement</i> )	Hot asphalt concrete pavement, grading C – 610.7 ton			
-----	--	--	--	--	--

**DIVISION 500 - Rigid Pavement**

501	Portland Cement Concrete Pavement	Reinforced rigid pavement, 8-inch depth, type C Smoothness – 273.5 sqyd
-----	-----------------------------------	--

**DIVISION 600 – Incidental Construction**

602	Culverts & Drains ( <i>indicate one or both</i> )	18-inch pipe culvert – 5.1 lnft
605	Underdrains, Sheet Drains & Pavement Edge Drains ( <i>culverts &amp; drains</i> ) ( <i>indicate which</i> )	Standard underdrain system – 320.4 lnft
609	Curb & Gutter ( <i>concrete – minor structures</i> ) ( <i>indicate which</i> )	Curb, stone, type 1, 6-inch depth – 110.2 lnft
615	Sidewalks, Drive Pads & Paved Medians ( <i>concrete – minor structures</i> )	Median, exposed aggregate concrete – 42 sqyd  Detectable warning panels – 1.3 sqyd
619	Fences, Gates & Cattle Guards	Bollard post – 2 each
622	Rental Equipment	x   YES     NO
624	Topsoil ( <i>landscaping &amp; related items</i> )	Placing conserved topsoil, 4-inch depth – 1740 sqyd
633	Permanent Traffic Control Devices ( <i>traffic control devices</i> )	Sign system – 125.5 sqft  Post, wood, 8-inch diameter – 1 each  Remove and reset sign – 4 each
634	Permanent Pavement Markings ( <i>traffic pavement markings</i> )	Type B, solid (white) – 2654 lnft  Type B, solid (yellow) – 3701 lnft  Type B, broken (white) – 290  Type B, accessibility – 1 each

<p>635 Temporary Traffic Control (<i>traffic control – flaggers &amp; pilot cars</i>)</p>	<p>Drum – 90 each</p> <p>Pavement markings – 1147 lft</p> <p>Pavement marking removal – 1147 lft</p> <p>Construction sign – 138.5 sqft</p>
<p>636 Signal, Lighting, &amp; Electrical Systems</p>	<p>Traffic detector wire loop – 1 each</p> <p>Conduit, 3/4-inch PVC – 142.6 lft</p> <p>Conduit, 1-inch PVC – 455.8 lft</p> <p>Conduit, 2-inch PVC – 44.7 lft</p> <p>Pole (Temporary with disconnect switch) – 1 each</p> <p>Utility box, junction box – 5 each</p>