

Date: 10/10/2007 **Solicitation No.:** DTFH70-08-R-00006
(Contracts use only)

DESCRIPTION OF PROJECT:

Project Number: MT NPS ERFO 2007(1)-45(3)

Project Name: GRST MP 33 Permanent ERFO Repairs

Project Length: 0.398 **Kilometers or Miles** (circle one)

Description & type of Work: This work consists of grading, base, paving, structures, and drainage. _____

LOCATION:

FOREST, PARK, BLM DIST, etc. Glacier National Park

COUNTY Glacier **STATE** Montana

THIS PROJECT IS LOCATED APPROXIMATELY:

16.0 **Kilometers/Miles** (circle one) West

of St. Mary Montana
(City) (State)

PRICE RANGE:

X \$5 million to \$7 million

CONTRACT TIME – The Government Estimate is based on:

SCHEDULE
(indicate # of schedules)

FIXED COMPLETION
DATE
(required information)

One Schedule July 1, 2008

DESCRIPTION OF WORK (check one): **US CUSTOMARY UNITS****DIVISION 150 – Project Requirements**

152	Construction Survey & Staking	X	YES		NO
153	Contractor Quality Control and Assurance	X	YES		NO
154	Contractor Sampling & Testing	X	YES		NO
155	Schedules for Construction Contracts (<i>construction schedules</i>)	X	YES		NO

DIVISION 200 – Earthwork

DI VI SI ON 200 – Ear thw ork 204	Excavation & Embankment				
					Roadway Excavation 1645 cuyd Embankment 590 cuyd
205	Rock Blasting: Controlled Blast Hole (<i>rock blasting</i>)				
	Blasting Consultant (<i>Consultant/Engineering Services</i>)	X	Yes		No
207	Earthwork Geotextiles (<i>geotextiles</i>)				Type II-A 460 sqyd Type I-A 532 sqft

DIVISION 250 - Slope Reinforcement and Retaining Walls

251	Riprap				Placed riprap, class 4 - 224 cuyd Placed riprap, class 6 - 1630 cuyd
255	Mechanically Stabilized Earth Walls (<i>retaining walls</i>)				2906 sqft
259	Soil Nail Retaining Walls				218 sqyd Soil Nails 6360 Inft Verification Test - 4 ea

DIVISION 300 – Aggregate Courses

301	Untreated Aggregate Courses (<i>crushed aggregate</i>)				Aggregate surface course- 410 tons
308	Minor Crushed Aggregate (<i>crushed aggregate</i>)				410 tons
310	Recycled Aggregate Course (<i>asphalt pavement recycling</i>)				5884 sqyd

DIVISION 400 – Asphalt Pavements & Surface Treatments

404	Minor Hot Asphalt Concrete (<i>asphalt concrete pavement</i>)				951 tons
-----	---	--	--	--	----------

DIVISION 600 – Incidental Construction

602	Culverts & Drains (<i>indicate one or both</i>)	Relocate Structures: 48” CMP – 80 Inft Inlets – 2 each
605	Underdrains, Sheet Drains & Pavement Edge Drains (<i>culverts & drains</i>) (<i>indicate which</i>)	Standard Underdrain – 494 Inft
620	Stone Masonry	Ashlar Guardwall Type 1 – 339 Inft Veneer – 823 sqyd
622	Rental Equipment	X YES NO
623	General Labor	General Labor 40 hr Blaster 150 hr Avalanche Spotter 300 hr
634	Permanent Pavement Markings (<i>traffic pavement markings</i>)	Type B Solid White 556 Inft Type B Solid Yellow 8400 Inft
635	Temporary Traffic Control (<i>traffic control – flaggers & pilot cars</i>)	Barricade, Type 3 - 12 ea 28 inch Tubular Markers – 40 ea Drums – 10 ea Moving Conc. Barriers – 90 ea Construction Sign – 219 sqft
Flagger:	Hours: 800	Pilot Car: Hours: 300
646	Buildings and Fixtures (<i>use pay item description</i>)	Portable Toilet 1 ea Toilet Maintenance 1 ea