

GENERAL CONSTRUCTION NOTES

1. Construction signage shall be an incidental cost to the project, cost shall be borne by the Contractor. Signs shall conform to the Manual on Uniform Traffic Control Devices (MUTCD) published by the U.S. Department of Transportation, Federal Highway Administration. All construction signing will be completed and approved prior to the beginning of construction.

2. All disturbed areas shall be seeded, this work shall be considered incidental to Section 24901 – Composite Road Construction – no extra payment will be given. The following seed mix and spread rate shall be used.

<u>Species of Seed</u>	<u>Percent Live Seed / Pounds Per Acre</u>
Slender Wheatgrass	5.0
Western Wheatgrass	4.0
Idaho Fescue	3.0
Sheep Fescue	3.0

3. Section 20301 – Removal of Structures and Obstructions – The cattleguard and wood posts shall be disposed at a State-approved landfill.



U.S. DEPARTMENT OF AGRICULTURE
FOREST SERVICE
R-2
 ROCKY MOUNTAIN REGION

Designed By: <u>SEL</u>	Date: <u>2/08</u>
Drawn By: <u>SEL</u>	Date: <u>2/08</u>
Checked By: _____	Date: _____

Revisions		
No.	Date	By

Forest WHITE RIVER NATIONAL FOREST	Project Name KEYSTONE STEWARDSHIP
--	---

Sheet Title GENERAL NOTES	Sheet 4 OF 8
Scale AS SHOWN	