Mile Post (MP)	Work List Description - NFSR 66.1
2.15	End furnish and install CDOT class 6 aggregate for a 4" depth.
2.20	Reconstruct rolling water dip.
2.21	Reconstruct rolling water dip.
2.27	Reconstruct rolling water dip.
2.30	Reconstruct rolling water dip.
	Begin furnish and install CDOT class 6 aggregate for a 4" depth.
2.50	End furnish and install cdot class 6 aggregate for a 4" depth.
	Spur on right.
2.52	Reconstruct rolling water dip.
2.55	Reconstruct rolling water dip.
2.60	Reconstruct rolling water dip.
2.62	Existing Switchback
2.65	Reconstruct rolling water dip.
2.70	Reconstruct rolling water dip.
2.72	Reconstruct rolling water dip.
2.75	Reconstruct rolling water dip.
2.80	Reconstruct rolling water dip.
2.83	Reconstruct rolling water dip.
2.85	Remove 1 rolling water dip, reconstruct 1 rolling water dip.
2.90	Existing Grade dip.
2.93	Construct rolling water dip.
2.95	Remove rolling water dip on the curve.
3.00	Remove rolling water dip, (on the same curve)
3.05	Reconstruct rolling water dip.
3.10	Reconstruct rolling water dip.
3.15	Reconstruct rolling water dip.
3.20	Reconstruct rolling water dip. Borrow source on left.
3.22	Install 4" road base using borrow source from MP 3.2.

Mile Post (MP)	Work List Description - NFSR 66.1
3.30	End road reconditioning for NFSR 66.1.

U.S. DEPARTMENT OF AGRICULTURE
FOREST SERVICE
R-2
ROCKY MOUNTAIN REGION

Designed By: SEL Date: 2/08
Drawn By: BKC Date: 2/08
Checked By: Date:

Revisions

No.	Date	By	Description

Forest: WHITE RIVER NATIONAL FOREST
Project Name: KEYSTONE STEWARDSHIP

Sheet Title: ROAD NO. 66.1 WORK LIST
Scale: AS SHOWN
Sheet: 8 OF 8