

**DESCRIPTION OF PROJECT:**

**Project Number:** WA FS ERFO 2007(1)-22(1)

**Project Name:** Mt St Helens District Repairs FR 23 MP 34.95

**Project Length:** 0.054 **Kilometers or Miles** (circle one)

**Description & type of Work:** This work consists of Grading, culvert and aggregate surfacing  
-

**LOCATION:**

**FOREST, PARK, BLM DIST, etc.** Gifford Pinchot National Forest

**COUNTY** Skamania **STATE** Washington

**THIS PROJECT IS LOCATED APPROXIMATELY:**

17 Kilometers **Miles** North (Direction, i.e., North, NW, etc.)

of Trout Lake Washington  
(City) (State)

**PRICE RANGE:**

x Under \$500,000

**CONTRACT TIME – The Government Estimate is based on:**

**SCHEDULE**

1 **One Schedule**

**DESCRIPTION OF WORK:**

☒ **US CUSTOMARY UNITS**

**DIVISION 150 – Project Requirements**

|     |  |                        |     |  |    |
|-----|--|------------------------|-----|--|----|
| 152 | Construction Survey & Staking  | x                      | YES |  | NO |
| 154 | Contractor Sampling & Testing  | x                      | YES |  | NO |
| 155 | Schedules for Construction Contracts ( <i>construction schedules</i> ) | x                      | YES |  | NO |
| 157 | Soil Erosion Control Devices ( <i>erosion control devices</i> )        | 340 lnft straw wattles |     |  |    |

**DIVISION 200 – Earthwork**

|     |  |                     |  |  |  |
|-----|--|---------------------|--|--|--|
| 201 | Clearing & Grubbing  | LPSM                |  |  |  |
| 203 | Removal of Structures & Obstructions ( <i>structures, demolition</i> ) | Remove pipe culvert |  |  |  |
| 204 | Excavation & Embankment  | 117 cuyd            |  |  |  |
| 207 | Earthwork Geotextiles ( <i>geotextiles</i> )                           | 100 sqyd            |  |  |  |

**DIVISION 250 - Slope Reinforcement and Retaining Walls**

|     |        |          |  |  |  |
|-----|--------|----------|--|--|--|
| 251 | Riprap | 151 cuyd |  |  |  |
|-----|--------|----------|--|--|--|

**DIVISION 300 – Aggregate Courses**

|     |  |          |  |  |  |
|-----|--|----------|--|--|--|
| 308 | Minor Crushed Aggregate ( <i>crushed aggregate</i> ) | 250 tons |  |  |  |
|-----|--|----------|--|--|--|

**DIVISION 600 – Incidental Construction**

|     |   |                                  |  |  |  |
|-----|---|----------------------------------|--|--|--|
| 602 | Culverts & Drains ( <i>indicate one or both</i> )                     | 144 LNFT                         |  |  |  |
| 625 | Turf Establishment ( <i>indicate seeding or mulching separately</i> ) | 1114 sqyd seed and mulching each |  |  |  |