

ID PFH 9(5), Enaville-Thompson Pass Road, Idaho Panhandle National Forest, Shoshone County, Idaho

The work consists of Subexcavation, base and paving and other small items of work.

Project length: 12.9 Miles

Fixed Completion Date: October 31, 2009

Estimated Price Range: \$7 Million to \$10 million

Location: 32 miles East of Couer d'Alene, ID

DESCRIPTION OF WORK in US CUSTOMARY UNITS

DIVISION 150 – Project Requirements

152	Construction Survey & Staking	X	YES		NO
153	Contractor Quality Control and Assurance	X	YES		NO
154	Contractor Sampling & Testing	X	YES		NO
155	Schedules for Construction Contracts (<i>construction schedules</i>)	X	YES		NO
157	Soil Erosion Control Devices (<i>erosion control devices</i>)	24.5 ACRE			

DIVISION 200 – Earthwork

201	Clearing & Grubbing (Clearing)	24.5 ACRE			
204	Excavation & Embankment (Subexcavation) (Select Borrow)	5756 CUYD 8164 TON			
207	Earthwork Geotextiles (<i>geotextiles</i>)	70600 SQYD			

DIVISION 300 – Aggregate Courses

303	Road Reconditioning (Ditch Reconditioning)	43000 LNFT			
308	Minor Crushed Aggregate (<i>crushed aggregate</i>)	3000 TON			
310	Recycled Aggregate Course (<i>asphalt pavement recycling</i>)	7134 SQYD			

DIVISION 400 – Asphalt Pavements & Surface Treatments

401	Superpave Hot Asphalt Concrete Pavement	39934 TON			
404	Minor Hot Asphalt Concrete (<i>asphalt concrete pavement</i>)	4055 TON			
411	Asphalt Prime Coat (<i>asphalt surface treatment</i>)	10 TON			
412	Asphalt Tack Coat (<i>asphalt surface treatment</i>)	100 TON			
413	Asphalt Pavement Milling	300 SQYD			
416	Continuous Cold Recycled Asphalt Base Course (<i>asphalt pavement recycling</i>)	200000 SQYD			

DIVISION 600 – Incidental Construction

605	Underdrains, Sheet Drains & Pavement Edge Drains (<i>culverts & drains</i>) (indicate which)	3100 LNFT			
617	Guardrail	2050 LNFT			
622	Rental Equipment	X	YES		NO
625	Turf Establishment (<i>indicate seeding or mulching separately</i>)	49 SLRY			
633	Permanent Traffic Control Devices (Sign System) (Delineator, Type 4F White) (Delineator, Type 4F Yellow)	75 SQFT 104 EACH 2 EACH			
634	Permanent Pavement Markings (<i>Type A, Solid Yellow</i>) (<i>Type A, Broken Yellow</i>) (<i>Type A, Solid White</i>)	210000 LNFT 53000 LNFT 275000 LNFT			
635	Temporary Traffic Control (Cone, Type 36-Inch) (Drum) (Pavement Markings) (Construction Sign) (Traffic And Safety Supervisor)	700 EACH 100 EACH 210000 LNFT 207 SQFT 70 DAY			
Pilot Car:		Hours:600			
Flagger		Hours: 600			