

Date: June 13, 2008

Solicitation No.: DTFH70-08-R-00023
(Contracts use only)

DESCRIPTION OF PROJECT:

Project Number: WA FS ERFO 2007(1)-22(2)

Project Name: Mt St Helens District Repairs FR 83 MP 6.9 to 11.3

Project Length: 4.40 Miles

Description & type of Work: This work consists of Emergency repairs, debris removal, drainage, riprap, aggregate, and asphalt.

LOCATION:

FOREST, PARK, BLM DIST, etc. Gifford Pinchot National Forest

COUNTY Skamania STATE Washington

THIS PROJECT IS LOCATED APPROXIMATELY:

14 Miles NE
of Cougar Washington
(City) (State)

PRICE RANGE:

x Under \$500,000

CONTRACT TIME – The Government Estimate is based on:

FIXED COMPLETION

SCHEDULE

(indicate # of schedules)

DATE

(required information)

1 **One Schedule** 9/29/2008

DESCRIPTION OF WORK:

US CUSTOMARY UNITS

DIVISION 150 – Project Requirements

152	Construction Survey & Staking	x	YES		NO
153	Contractor Quality Control and Assurance	x	YES		NO
154	Contractor Sampling & Testing	x	YES		NO
155	Schedules for Construction Contracts (<i>construction schedules</i>)	x	YES		NO
157	Soil Erosion Control Devices (<i>erosion control devices</i>)				600 lft sediment wattles, temporary stream diversion

DIVISION 200 – Earthwork

203	Removal of Structures & Obstructions (<i>structures, demolition</i>)	Pipe culvert, trail bridge
204	Excavation & Embankment	8676 cuyd exc

DIVISION 250 - Slope Reinforcement and Retaining Walls

251	Riprap	343 tons class 4
-----	--------	------------------

DIVISION 300 – Aggregate Courses

308	Minor Crushed Aggregate (<i>crushed aggregate</i>)	879 tons
-----	--	----------

DIVISION 400 – Asphalt Pavements & Surface Treatments

404	Minor Hot Asphalt Concrete (<i>asphalt concrete pavement</i>)	310 tons
-----	---	----------

DIVISION 600 – Incidental Construction

602	Culverts & Drains (<i>indicate one or both</i>)	60 lft 24 inch
603	Structural Plate Structures (<i>culverts & drains</i>)	94 lft 180 inch
622	Rental Equipment	x YES NO
625	Turf Establishment (<i>indicate seeding or mulching separately</i>)	1,500 sqyd Seeding and mulching
634	Permanent Pavement Markings (<i>traffic pavement markings</i>)	3900 lft
	Other 616 Slope Paving	46 SQYD slope paving