

LEGEND

LIGHT POLE

EXISTING

FIRE HYDRANT

WATER VALVE

SANITARY SEWER MANHOLE

MITERED END SECTION — W — BURIED WATER LINE

--- W--- BURIED WATER LINE PER FIELD MARKINGS --- X --- 6' CHAIN LINK FENCE

BOLLARD

INVERT EL ELEVATION

IE INVERT ELEVATION SMH SANITARY SEWER MANHOLE

MES MITERED END SECTION

PAVEMENT

ASPHALT TO BE REMOVED

4 CONCRETE

<u>NEW</u>

₩ WATER VALVE

 $\begin{array}{c|cccc} x & x \\ x & x \end{array}$ AREAS TO BE SODDED

GENERAL NOTES:

TO BE ADJUSTED OR REPLACED.


* ALL DISTURBED AREAS (AS A RESULT OF CONSTRUCTION) TO BE STABILIZED WITH CENTIPEDE SOD AS SHOWN, AND SEEDED AND MULCHED ELSEWHERE. * THE LOCATIONS OF UTILITIES ARE APPROXIMATE AND SHALL BE VERIFIED BY THE OWNER OR IT'S REPRESENTATIVE. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK, AND IS RESPONSIBLE FOR ANY AND ALL DAMAGES CAUSED BY THE CONTRACTOR'S FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES. * CONTRACTOR SHALL CLEAN OUT ACCUMULATED SILT IN SWALES DURING

* CONTRACTOR SHALL MAINTAIN RECORD DRAWINGS DURING CONSTRUCTION WHICH SHOWS AS-BUILT CONDITIONS OF ALL WORK INCLUDING PIPING, DRAINAGE BASINS, STRUCTURES, ETC. THESE RECORD DRAWINGS SHALL BE SUBMITTED TO THE GOVERNMENT.

* NO DEVIATIONS OR REVISIONS FROM THESE PLANS BY THE CONTRACTOR SHALL BE ALLOWED WITHOUT PRIOR WRITTEN APPROVAL FROM THE CONTRACTING OFFICER. * IT IS THE CONTRACTOR'S SOLE RESPONSIBILITY TO PROVIDE EROSION AND SEDIMENTATION BEST MANAGEMENT PRACTICES DURING CONSTRUCTION. THOSE SHOWN ON THE PLANS ARE THE MINIMUM CONTROL MEASURES TO BE TAKEN. THE CONTRACTOR SHALL, DURING CONSTRUCTION, INSPECT AND REPAIR ALL EROSION/SEDIMENT CONTROL STRUCTURES PER FDEP AND EPA STANDARDS. THE CONTRACTOR SHALL EMPLOY A CERTIFIED FLORIDA STORMWATER EROSION/SEDIMENTATION INSPECTOR AND MAKE ANY AND ALL REQUIRED

INSPECTIONS AS NECESSARY PER FDEP AND EPA STANDARDS. * CLEAR & GRUB AS REQUIRED TO CONSTRUCT BUILDING, INCLUDING TREES WITHIN

20' OF BUILDING. CLEAR ALL AREAS TO RECEIVE SOD. * THE CONTRACTOR SHALL PROTECT THE EXISTING IRRIGATION SYSTEM AS MUCH AS POSSIBLE AND SHALL REPAIR WHERE DAMAGED. EXISTING SYSTEM SHALL BE EXTENDED TO SERVE NEW GRASSED AREAS AND BE MODIFIED WHERE HEADS NEED



MARCH 20, 2009 DESIGNED BY:

WAREHOUSE

CONSTRUCT
1 SOCS

 \mathcal{D}

AIR FORCE SPECIAL
PERATIONS COMMAND
1 SPECIAL OPERATIONS
CIVIL ENGINEERING SQUADRON
HURLBURT FIELD, FLORIDA

DRAWN BY: BUILDING NO.:

PROJECT NO.:

FTEV 05-1076



2 OF 26