

STATE	FOREST	PROJECT NAME	SHEET	SHEETS
IDAHO	CLW	SADDLE CAMP ROAD DECOMMISSIONING	2	14

SUMMARY OF ESTIMATED QUANTITIES

FOR INFORMATIONAL PURPOSES ONLY

ROAD DECOMMISSIONING

NO. ITEM	ITEM DESCRIPTION	UNIT	75737	75740	75741	75742	75743	75744	860550	860551	TOTAL	
			0-1.77	0-0.63	1.1-2.35	0-1.52	0-0.57	0-0.88	0-0.24	0-0.84		
15101	MOBILIZATION	LS	ALL REQUIRED									1
20301	REMOVAL OF METAL CULVERTS	EACH	2	0	3	0	0	2	0	0	7	
21103A	ROADWAY OBLITERATION, METHOD I	MI	1.77	0.63	0	0	0.57	0.88	0.24	0.84	4.93	
21103B	ROADWAY OBLITERATION, METHOD II	MI	0	0	1.25	0.52	0	0	0	0	1.77	
62201	HYDRAULIC EXCAVATOR WITH THUMB	HOURL	0	0	4	0	2	4	2	4	16	

NOTES

- ITEM 15707 STRAW BALES ARE TO BE USED FOR EROSION CONTROL FOR SUCH THINGS AS CHECK DAMS AND MULCH AS DIRECTED BY THE C.O.
- ITEM 20301 ALL METAL CULVERT DESIGNATED FOR REMOVAL SHALL BECOME THE PROPERTY OF THE CONTRACTOR AND BE REMOVED FROM FOREST LAND AND DISPOSED OF IN A LEGAL MANNER.
- ITEM 21103 CONTRACTOR SHALL PROVIDE AT LEAST ATV ACCESS FOR THE FOREST SERVICE INSPECTORS TO THE ENTIRE ROAD BEING DECOMMISSIONED.
- ITEM 21103 ALL LIVE STREAMS WILL REQUIRE EITHER THE EXISTING CULVERT OR A TEMPORARY CULVERT WHEN CROSSING FOR ACCESS AND WILL REQUIRE DEMATERING OR STREAM DIVERSIONS WHEN DOING CHANNEL WORK.
- ITEM 21103 ROAD OBLITERATION METHODS VARY BY INDIVIDUAL ROAD AND ARE SPECIFICALLY NOTED ON THE WORK LISTS.
- ITEM 21103 WORKLISTS ARE DETERMINED FROM OLD SURVEYS AND WORK LISTED IS A BEST ESTIMATE. CONDITIONS MAY HAVE CHANGED ON THE GROUND.
- ALL REQUIREMENTS OF SPECIFICATION 211 SHALL BE MET.
- ITEM 62201 EQUIPMENT RENTAL WORK IS FOR UNFORSEEN SITUATIONS. ALL WORK WILL BE APPROVED BY THE C.O. PRIOR TO EXECUTION. THIS ITEM MAY NOT BE USED IN ITS ENTIRETY.