

WA PRA-MORA 10(11), SR 123-2 AND SR 410-1C, MOUNT RAINIER NATIONAL PARK, PIERCE COUNTY, WASHINGTON.

THE WORK CONSISTS OF: GRADING, DRAINAGE, BASE, WALL STABILIZATION, STONE MASONRY, AND PAVING ROADWAY AND TURNOUTS.

PROJECT LENGTH: 7.33 MILES

FIXED COMPLETION DATE: OCTOBER 30, 2008

ESTIMATED PRICE RANGE: \$5 MILLION TO \$7 MILLION

LOCATION: APPROXIMATELY 18 MILES NORTHEAST OF PACKWOOD, WASHINGTON

DESCRIPTION OF WORK IN US CUSTOMARY UNITS:

DIVISION 150 – Project Requirements

152	Construction Survey & Staking	X	YES		NO
153	Contractor Quality Control and Assurance	X	YES		NO
154	Contractor Sampling & Testing	X	YES		NO
155	Schedules for Construction Contracts (<i>construction schedules</i>)	X	YES		NO
157	Soil Erosion Control Devices (<i>erosion control devices</i>) Silt fence				5,000 FT

DIVISION 200 – Earthwork

201	Clearing & Grubbing				8,000 SQYD
204	Excavation & Embankment				4,200 CUYD
207	Earthwork Geotextiles (<i>geotextiles</i>)				22,000 SQYD
211	Roadway Obliteration				2,000 SQYD

DIVISION 250 - Slope Reinforcement and Retaining Walls

251	Riprap				120 CUYD
-----	--------	--	--	--	----------

DIVISION 300 – Aggregate Courses

301	Untreated Aggregate Courses (<i>crushed aggregate</i>)				4,000 TON
310	Recycled Aggregate Course (<i>asphalt pavement recycling</i>)				5,400 CUYD

DIVISION 400 – Asphalt Pavements & Surface Treatments

401	Superpave Hot Asphalt Concrete Pavement				12,600 TON
411	Asphalt Prime Coat (<i>asphalt surface treatment</i>)				1 TON
412	Asphalt Tack Coat (<i>asphalt surface treatment</i>)				2 TON
416	Continuous Cold Recycled Asphalt Base Course (<i>asphalt pavement recycling</i>)				124,600 SQYD

DIVISION 550 – Bridge Construction

565	Drilled Shafts				2,000 LNFT
-----	----------------	--	--	--	------------

DIVISION 600 – Incidental Construction

602	Culverts & Drains (<i>indicate one or both</i>) CULVERTS				300 LNFT
605	Underdrains, Sheet Drains & Pavement Edge Drains (<i>culverts & drains</i>) (<i>indicate which</i>) UNDERDRAINS				1,950

610	Horizontal Drains				400 LNFT
615	Sidewalks, Drive Pads & Paved Medians (concrete – minor structures)				217 SQYD
617	Guardrail				600 LNFT
622	Rental Equipment	X	YES		NO
625	Turf Establishment <i>MULCHING</i>				8,000 SQYDS
634	Permanent Pavement Markings (<i>traffic pavement markings</i>)				115,000 LNFT
Flagger:	Hours: 4,000	Pilot Car:		Hours: 400	
Other 620	STONE MASONRY				500 SQFT