

### QUESTION SET 1

**Question:** RE: Cover appendix 3.1.4. – demo / disposal – please define “excess.” I can easily quote the demo and movement of the materials across the street as stated – however not knowing if there will be materials not accepted at the DLADS center makes it a little tough to prepare a cost for this line item.

**Answer:** DLADS is likely to accept any items that can be reused or recycled, such as the metal from the existing racking. Excess may include the wooden decking and wooden end panels on the existing pallet rack, any trash produced on site, etc.

**Question:** RE: cantilever – DS - “A” back to “B” – it appears drawn using separate towers for this configuration – is that required?

**Answer:** As long as the uprights meet or exceed the specifications, double-sided uprights can be used. The capacity of each arm multiplied by the number of arms attached to the upright shall determine the capacity of the upright.

**Question:** RE: dwg S3 of S3 – bldg. 3122, there is pallet rack drawn into this bldg. space – please confirm this is NIC.

**Answer:** Racking shown in Bldg. 3122 is existing and is not included in this contract. The vertical carousel is the only equipment to be provided and installed in Bldg. 3122.